BANGALORE DIVISION.

Notification dated 16th January 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 1st February 1936, for the maintenance work to Santhemogenahalli Tank, Register No. 123 of Channapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the maintenance work to Santhemogenahalli Tank, Register No. 123 of Channapatna Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract quantities for the maintenance work of Santhe mogenahally Major Tank Register No. 123, Channapatna Taluk.

No.	Items of work	Per	Quantity	Rate	Rate in	
					Words	Figures
1	Clearing Jungle thickly grown	Grade	70	1 0 0		
2	Cutting grips on slopes and top of bend ..	,,	70	2 0 0		
3	Removing ant-hills and filling with sand ..	No.	50	1 0 0		
4	Earthwork raising bund to R. L. 55·00 with watering and consolidating	C.yds.	8,716	0 4 0		
5	Turfing the slopes of bund and watering till it is satisfactory	S.yds.	16,193	0 1 0		
6	Providing new grade stones with cutting figures and painting, etc., complete including fixing with bed slabs ..	No.	42	1 8 0		
7	Removing and refixing the old grade stones with painting, etc., complete ..	,,	28	0 6 0		
8	Providing and fixing B. M. stones with cutting figures and painting, etc., including bed slabs	,,	2	2 0 0		
9	Providing and fixing new Index stones ..	,,	70	0 6 0		
10	Providing and fixing new Register No. stones with cutting figures and painting, including bed slabs	,,	1	2 12 0		
11	Lead charges for carrying the earth from the weir draft and approaches, including consolidation	C.yds.	1,170	0 1 6		

Notification dated 16th January 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 1st February 1936, for constructing one block of Linemen Quarters at Harohalli at 24th mile on Bangalore-Mysore Road *via* Kankanhalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Linemen Quarters at Harohalli, Kankanhalli Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities measurements, quality of works, etc., and in all disputes on any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing one Block of Linemen Quarters at Harohally 24th mile on Bangalore-Mysore Road, *via* Kankanhalli as per type plan No. G. 381.

Sl. No.	Items of work	Unit	Quantity	Rate	Rate in	
					Words	Figures
1	Earthwork excavation and filling in basement	C.yd.	33	0 4 0		
2	Burnt stone jelly concrete in lime mortar filling in foundation	C.ft.	287	0 3 9		
3	Burnt size stone masonry in clay foundations and basement	,,	897	0 4 0		
4	Burnt brick in clay superstructure ..	,,	1,689	0 3 6		
5	Do in mortar do ..	,,	380	0 4 3		
6	Burnt stone slabs 4" thick, roughly dressed and set in mortar	S.ft.	63	0 4 0		
7	Do 6" thick do ..	,,	109	0 6 0		
8	Binding wall 6"×6" of burnt brick in lime mortar plastered and whitewashed, etc., complete	R.ft.	28	0 5 0		
9	Plastering with chunam, 2 coats ..	Sqr.	44·63	3 0 0		
10	Pointing with chunam	,,	1.45	1 8 0		
11	White and colour washing, 2 coats ..	,,	46·08	0 5 0		
12	Ridge tiles set in mortar and cement pointed	R.ft.	68	0 7 6		
13	Ventilating tiles set in mortar and cement pointed	No.	16	1 8 0		
14	Honney wood wrought and put up with two coats of wood oiling	C.ft.	48·76	3 12 0		
15	Door with teakwood frames and honney wood battened shutters 1" thick with iron fittings, etc., complete	S.ft.	78	1 6 0		

Sl. No.	Items of work	Unit	Quantity	Rate	Rate in Words	Rate in Figures
16	Windows with teakwood frames and honney wood battened shutters 1″ thick with $\frac{3}{4}$″ dia. iron bars and fittings, etc., complete	S.ft.	60	1 12 0		
17	Chocolate painting, 2 coats	Sqr.	3.06	4 0 0		
18	Constructing sinks in bath room ..	No.	4	6 0 0		
19	Providing stone mortar and pestle ..	,,	4	5 0 0		
20	Flooring with 1$\frac{1}{2}$″ cement concrete on 3″ lime concrete and plastered with $\frac{1}{2}$″ cement plaster, including cutting lines and mixed with red ochere	Sqr.	7.82	18 0 0		
21	Roofing with 1st class Mangalore Tiles on Teakwood reepers of 2″×1′ including wood oiling to reepers	,,	13.18	24 0 0		

M. A. SRINIVASACHARI,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 11th January 1936.

The attention of the public is hereby invited to the advertisement on page 81 of the *Mysore Gazette*, Part VI, dated 16th January 1936, calling for tenders for constructing a Primary School at Malladihalli, Holalkere Taluk.

H. V. VARADACHARYA,
Executive Engineer in Charge.

MEDICAL DEPARTMENT

OFFICE OF THE SUPERINTENDENT, MINTO OPHTHALMIC HOSPITAL, BANGALORE.

Abstract Notification dated 29th December 1935.

The attention of the public is invited to the detailed Notification, dated the 28th December 1935, regarding the sale of unserviceable articles at the Minto Ophthalmic Hospital, Bangalore, on Friday, the 31st January 1936, at 5 P.M.

B. K. NARAYANA RAO,
Superintendent.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE RESIDENCY SURGEON, CIVIL AND MILITARY STATION, BANGALORE.

Notice

Notice is hereby given that sealed tenders will be received on Monday the 3rd February 1936 by the Residency Surgeon, Bangalore, for the supply by contract of all articles of diet, etc., required for the use of the Bowring, Lady Curzon, Gosha, and Isolation hospitals, Bangalore, during the period from 1st April 1936 to 31st March 1937.

Forms of Tender (which also contain the specifications and conditions on which tenders will be considered and contracts let) can be had at the Office of the Residency Surgeon, Bowring Civil Hospital, Bangalore, on any day except Sundays between 8 A.M. and 12 NOON.

Each tender must be accompanied by a deposit (in Government Promissory Notes or Bank receipts) as earnest deposit money of the amount noted against each group. When several groups are tendered for, one Bank receipt for the total amount of earnest deposit money will be received. This earnest money will be returned to unsuccessful tenderers immediately and to the others as soon as they have lodged the security mentioned in para 9 of the Tender form. No cash will be received. In default of such deposit the tender will be rejected.

J. B. HANCE,
Lt.-Col., I.M.S.,
Residency Surgeon, Bangalore.